



CALUMPIT WATER DISTRICT

Calumpit, Bulacan

ANNUAL REPORT 2021

Calumpit Water District (CWD) continuously plans and implements various programs and services to maintain and improve its twenty-four hours (24/7) service to all Calumpiteños and nearby service areas.

I. LIST OF COMPLETED AND ON-GOING GOVERNMENT/PROJECTS/ACTIVITIES (PPA)

COMPLETED PROJECTS

NAME OF PROJECT	PROJECT COST (PHP)	LOCATION (Barangay)
1. Design, Supply, Construction, Testing and Commissioning of Two (2) units 500 cubic meter capacity Glass Fused to Steel Bolted Tank, Electromechanical Equipment and Appurtenances at Metropolis Subdivision (Sta. Lucia Realty)	16,910,000.00	Balite
2. Design and Drilling of One (1) Production Well at barangay Frances "Bukid"	3,358,800.00	Frances
3. Installation of New Parallel Pipelines at barangay Frances "Bukid"	3,863,299.00	Frances
4. Construction of Frances "Bukid" Pumping Station	8,034,803.00	Frances
5. Replacement of Existing Cast Iron (CI) Pipe Water Main at barangay Sucol	773,401.51	Sucol
6. Upgrading of Pipeline from 50mm PE to 75mm uPVC Pipe at barangay Sapang Bayan	619,443.00	Sapang Bayan
7. Supply, Installation, Monitoring, Operation and Maintenance of Logic Controller R-Tap (Intelligent Supply and Pressure Management) System For CWD's Water Supply Service Operation	1,850,000.00	Meysulao "Riverside" PS Calizon PS, Gatbuca PS and Danga PS

"CWD...Patuloy sa Serbisyo Publiko"



8. Supply of Labor, Materials and Equipments for the Design, Supply, Installation, Testing and Commissioning of One (1) Unit Panoramic Passenger/ Freight Elevator with Automatic Rescue Device, Voice Annunciator

3,500,000.00

CWD Administration Building

9. Construction of New Storage Room and Parking Space

789,968.67

CWD Administrations Building

ON-GOING PROJECTS

NAME OF PROJECT	PROJECT COST (PHP)	LOCATION (Barangay)
1. Replacement of Existing 75mm PE Pipe to 75mm uPVC Pipe affected by upgrading of road at Pulong David barangay Meysulao	453,706.00	Meysulao
2. Installation of New Transmission Pipelines along Calumpit-Hagonoy road at barangay Balungao	2,231,628.10	Balungao

II. CWD SERVICE CONNECTION

1. Total Number of Service Connections	:	26,759
2. Total Number of Active Connections	:	24,417
3. Service Barangay Coverage in Calumpit	:	29/29 (100%)
4. Average Monthly Consumption per Connection	:	21.4 cubic meter

III. CWD WATER PRODUCTION

1. Number of hours of water supply service	:	24/7
2. Total Number of Production Wells	:	21
3. Total Number of Fire Hydrants	:	89



Management System
ISO 9001:2015
www.tuv.com
ID: 5108613954



4. Total Length of Pipelines (km)	:	202.5km
5. % Metered Service Connection	:	100%
6. Production Capacity Utilized	:	79.18%
7. Non Revenue Water	:	23.44%

IV. CWD SOCIAL ADVOCACY

(Due to COVID-19 pandemic, the activities being conducted by the CWD as part of its Corporate Social Responsibility is still limited to avert the spread of the virus in the workplace and community)

In lieu of BISITA ESKWELA that regularly being conducted by CWD as part of its program for Water Sanitation and Hygiene (WASH) in different elementary schools in the municipality yearly, the CWD **constructed two (2) units of WASH BASIN at Doña Damiana De Leon Macam Memorial Elementary School located at barangay San Miguel and Panducot Elementary School located at barangay Panducot.** This is in preparation of their face to face classes to promote sanitation and proper hygiene and help avert the spread of COVID-19 among students in the said elementary schools.

Amid COVID 19 Pandemic, **CALUMPIT WATER DISTRICT** guided by its vision will continue to commit to the people of Calumpit and nearby service areas to: ensure adequate water resources; provide safe and potable water at affordable cost, and carry out sanitation services through competent and dedicated workforce strongly committed to protect the environment.

Engr. RONNIE B. LARGADO
General Manager